


N:\Design-Drafting\Clients - LP\Monsanto-P4 Production\1010076-Monsanto Phase 3 Tech Memo Rev2\021 Sheet Set\1010076D037-0



NOT TO SCALE

HYDROLOGICAL PROCESSES (WITH EXAMPLE FLUXES)

- (1) PRECIPITATION = 2.4 GPM/ACRE BASED ON 23.64 INCHES/YEAR AVERAGE
- (2) EVAPOTRANSPIRATION = ESTIMATED TO BE 1.2 TO 1.7 GPM/ACRE OR 50 TO 70% OF TOTAL PRECIPITATION (COMBINED EVAPOTRANSPIRATION)
- (3) RUNOFF = ESTIMATED TO BE 0.24 TO 0.48 GPM/ACRE OR 10 TO 20% OF TOTAL PRECIPITATION (BASED ON SLOPES FROM 2-33%)
- (4) INFILTRATION = ESTIMATED TO BE 0.36 TO 0.72 GPM/ACRE OR 15 OR 30% OF TOTAL PRECIPITATION
- (5) SEEPAGE = ESTIMATED TO BE 0.32 TO 0.65 GPM/ACRE BASED ON ASSUMED 10X HIGHER K COMPARED TO UNDERLYING UNIT
- (6) INFILTRATION TO ALLUVIUM = 0.04 TO 0.07 GPM/ACRE
- (7) INFILTRATION TO BEDROCK = 0.004 TO 0.007 GPM/ACRE (RATES ESTIMATED BASED ON MODELING AND ASSUMPTIONS)

GEOCHEMICAL/BIOLOGICAL PROCESSES


- (A) LEACHING OF SOLUBLE SELENIUM
- (B) OXIDATION OF SULFIDES
- (C) BIOLOGICAL REDUCTION OF SELENIUM AND ADSORPTION AND PRECIPITATION

WASTE ROCK DUMP LOCATIONS:


BALLARD - MWD080,MWD081,MWD083,MWD084,MWD082
HENRY - MWD087,MWD090,MWD086,MWD088,MWD085
ENOCH VALLEY - MWD092,MWD091

WELL LOCATIONS

- * ALLUVIAL - MMW010,MMW014,MMW012,MMW017,MW-15A,MW-16A
- ** WEATHERED DINWOODY- MMW007,MMW008,MMW013,MMW018
- *** DEEP DINWOODY - MMW022

2	ISSUED FOR REVISED FINAL	07/08	C.Faulk	C.Fowler	C.Faulk
REV. No.	REVISIONS	DATE	DESIGN BY	DRAWN BY	REVIEWED AND SIGNED BY
P4 PRODUCTION SOUTHEAST IDAHO MINE-SPECIFIC SELENIUM PROGRAM					
PROJECT: 2007 HYDROGEOLOGIC DATA REPORT					
DRAWING TITLE: CONCEPTUAL MODEL GENERIC EXTERNAL WASTE ROCK DUMP					
			Sheet <u>1</u> Of <u>1</u> Sheets		
SCALE: As Shown			DRAWING No. 7		

N:\Design-Drafting\Clients_LP\Monsanto-P4_Production\1010076-Monsanto Phase 3 Tech Memo Rev2\021 Sheet Set\1010076D038-0




HYDROLOGICAL PROCESSES


- (1) PRECIPITATION = 2.4 GPM/ACRE BASED ON 23.64 INCHES/YEAR AVERAGE
(2) EVAPOTRANSPIRATION = ESTIMATED TO BE 1.2 TO 1.7 GPM/ACRE OR 50 TO 70% OF TOTAL PRECIPITATION (COMBINED EVAPOTRANSPIRATION)
(3) RUNOFF = ESTIMATED TO BE 0.24 TO 0.48 GPM/ACRE OR 10 TO 20% OF TOTAL PRECIPITATION(BASED ON SLOPES FROM 2-33%)
(4) INFILTRATION = ESTIMATED TO BE 0.36 TO 0.72 GPM/ACRE OR 15 OR 30% OF TOTAL PRECIPITATION
(5) INFILTRATION TO BEDROCK = 0.004 TO 0.007GPM/ACRE (GROUNDWATER IN PIT MAY BE PERCHED)
(RATES ESTIMATED BASED ON MODELING AND ASSUMPTIONS)

GEOCHEMICAL/BIOLOGICAL PROCESSES

- (A) LEACHING OF SOLUBLE SELENIUM
(B) OXIDATION OF SULFIDES
(C) BIOLOGICAL REDUCTION OF SELENIUM AND ADSORPTION AND/OR PRECIPITATION


2	ISSUED FOR REVISED FINAL	07/08	C.Faulk	C.Fowler	C.Faulk	
REV. No.	REVISIONS	DATE	DESIGN BY	DRAWN BY	REVIEWED AND SIGNED BY	
P4 PRODUCTION SOUTHEAST IDAHO MINE-SPECIFIC SELENIUM PROGRAM						
PROJECT: 2007 HYDROGEOLOGIC DATA REPORT						
DRAWING TITLE: CONCEPTUAL MODEL GENERIC BACKFILLED MINE PIT						
				Sheet 1 Of 1 Sheets		
SCALE: As Shown				DRAWING No. 8		

N:\Design-Drafting\Clients -LP\Monsanto-P4 Production\1010076-Monsanto Phase 3 Tech Memo Rev2\021 Sheet Set\1010076D039-0



GEOCHEMICAL/BIOLOGICAL PROCESSES
(A) LEACHING OF SOLUBLE SELENIUM AND OXIDATION OF SULFIDES
(B) BIOLOGICAL REDUCTION OF SELENIUM AND ADSORPTION AND PRECIPITATION

WELL LOCATIONS
* UPPER WELLS FM.- MMW023,MMW020
** DEEPER WELLS FM. - MMW021

2	ISSUED FOR REVISED FINAL	07/08	C.Fouk	C.Fowler	C.Fouk	
REV. No.	REVISIONS	DATE	DESIGN BY	DRAWN BY	REVIEWED AND SIGNED BY	
P4 PRODUCTION SOUTHEAST IDAHO MINE-SPECIFIC SELENIUM PROGRAM						
PROJECT: 2007 HYDROGEOLOGIC DATA REPORT						
DRAWING TITLE: CONCEPTUAL MODEL GENERIC OPEN MINE PIT						
				Sheet <u>1</u> Of <u>1</u> Sheets		
SCALE: As Shown				DRAWING No. 9		